NOTES :-

1. FLOORING IN ALL ROOMS SHOULD BE OF VITRIFIED FLOOR TILES

2. PARTITION IN CHANGING ROOM SHOULD BE OF ALUMINIUM

3. DOORS IN LABOUR ROOM SHOULD BE OF ALUMINIUM

4. WALL TILES SHOULD BE AT MINIMUM 7FEET HEIGHT

PLINTH AREA OR BUILT UP AREA

GROUND FLOOR = 41.71sqm OR 448.79sqft.

District Medical & Health Officer
East Jaintia Hills District
Khliehriat

SCHEDULE OF DOORS

TYPE	WIDTH (mm)	HEIGHT (mm)	GROUND FL. (nos)
D	1000	2100	01
D1	800	2100	05
		TOTAL	06

SCHEDULE OF WINDOWS & VENTILATORS

TYPE	WIDTH (cm)	HEIGHT (m)	SILL (cm)	GROUND FL. (nos)
W	1200	1350	800	02
W1	600	1350	800	02
			TOTAL	04

TYPE	WIDTH (m)	HEIGHT (m)	SILL (m)	GROUND FL. (nos)
V	1200	550	2100	02
V1	600	550	2100	02
			TOTAL	04

PROJECT :

PROPOSED CONSTRUCTION OF LABOUR ROOM AT IONGKALUH SUB CENTRE, EAST JAINTIA HILLS

DATE:

SCALE : NTS

DWG NO.: 07/24/EJHills/ Iongkaluh/Arch/01

CONTENT: FLOOR PLAN

ALL DIMENSIONS ARE IN MM OR OTHERWISE MENTIONED.
DRAWINGS ARE MEANT TO BE READ ONLY.

PREPARED BY:		COUNTERSIGNED BY:		APPROVED BY:
JUNIOR ENGINEER HEW EAST JAINTIA HILLS	JUNIOR ENGINEER MHSSP EAST JAINTIA HILLS	DOCTOR INCHARGE HEALTH FACILITY, EAST JAINTIA HILLS	SDO HEALTH ENGINEERING WING, EAST JAINTIA HILLS	EXECUTIVE ENGINEER, HEALTH ENGINEERING WING, SHILLONG.